



# AIA<sup>®</sup> Document G701/CMa<sup>™</sup> – 1992

## Change Order - Construction Manager-Adviser Edition

<b>PROJECT</b> <i>(Name and address):</i> 885-Fairground Renovations 1406 Teal Rd. Lafayette, IN 47905	<b>CHANGE ORDER NUMBER:</b> BP4 885-001 <b>INITIATION DATE:</b> 7/15/2020	<b>OWNER:</b> <input checked="" type="checkbox"/> <b>CONSTRUCTION MANAGER:</b> <input checked="" type="checkbox"/> <b>ARCHITECT:</b> <input type="checkbox"/> <b>CONTRACTOR:</b> <input checked="" type="checkbox"/> <b>FIELD:</b> <input type="checkbox"/> <b>OTHER:</b> <input type="checkbox"/>
<b>TO CONTRACTOR</b> <i>(Name and address):</i> ESCO Communications 8940 Vincennes Circle Indianapolis, IN 46266	<b>PROJECT NUMBERS:</b> 885 / 885 <b>CONTRACT DATE:</b> August 22, 2019 <b>CONTRACT FOR:</b> 4P-Paging-Audio-Visual	

**THE CONTRACT IS CHANGED AS FOLLOWS:**

**EWO 885-097**

**Overview:**

- Two (2) Poles will be provided. Pole 1 will have three (3) Community R series speakers and Pole 2 will have one (1) Community R series speaker.
- The Horse Barn will have (2) Small Horns mounted to the structure.
- Cabling will route back to the existing PA Rack.
- A New Amplifier will be provide to serve the new speakers.
- The existing equipment will be re-configured to provide Audio paging to the new speakers. The speakers will all receive the same paging information as One paging Zone.
- A separate Electrical Contractor will need to install raceway as needed including raceway up the poles to the speaker locations.
- Surge protectors will be located at the equipment rack and installed on the speaker lines.

**Scope of Work - New Era Technologies (ESCO Communications) will provide:**

- Cabling for Electrical Contractor to install to new Speakers (EC pricing not included).
- Installation of speakers on poles and in Horse Barn (Poles provided and installed by others).
- System drawings - Update to project As-builts and submittals.
- System Configuration
- One (1) year warranty
- All labor provided during normal 7:00AM to 3:30PM business hours

Electrical Contractor or others will need to provide (Not included in our estimate):

- Provide and install conduit if necessary – including raceway up pole to speaker locations.
- Provide ground wires for surge protectors.
- Install New Era provided speaker cable.
- Provide and install Poles.

Total INCREASE for this Change Order:

\$17,570.00

**CHANGE ORDER BP4 885-001 (EWO 885-097)**

The original Contract Sum was	\$	221,270.00
Net change by previously authorized Change Orders	\$	0.00
The Contract Sum prior to this Change Order was	\$	221,270.00 ✓
The Contract Sum will be increased by this Change Order in the amount of	\$	17,570.00
The new Contract Sum including this Change Order will be	\$	238,840.00


The Contract Time will be unchanged by Zero (0) days.  
 The date of Substantial Completion as of the date of this Change Order therefore is unchanged..

NOTE: This summary does not reflect changes in the Contract Sum, Contract Time or Guaranteed Maximum Price which have been authorized by Construction Change Directive.

**NOT VALID UNTIL SIGNED BY THE OWNER, CONSTRUCTION MANAGER, ARCHITECT AND CONTRACTOR.**

Tecton Construction Management  
 CONSTRUCTION MANAGER (Firm name)  
 102 North 3rd Street  
 Suite 201  
 Lafayette, IN 47901

NA  
 ARCHITECT (Firm name)  
 NA

ADDRESS  


ADDRESS

BY (Signature)  
 Mike Roberts  
 (Typed name) DATE: 7/20/2020

BY (Signature)  
 NA  
 (Typed name) DATE: NA

ESCO Communications  
 CONTRACTOR (Firm name)  
 8940 Vincennes Circle  
 Indianapolis, IN 46266

Tippecanoe County Commissioners  
 OWNER (Firm name)  
 20 N. Third Street  
 Lafayette, IN 47901

ADDRESS  


ADDRESS

BY (Signature)  
 Mike Lowe  
 (Typed name) DATE: 7-15-20

BY (Signature)  
 David Byers  
 (Typed name) DATE: