

Stewart W. Kline, P.E. Executive Director Mike Spencer, Assistant Executive Director

20 North Third Street Lafayette, IN 47901 Phone: (765) 423-9210 Fax: (765) 423-9127

EVALUATION OF TIPPECANOE COUNTY BRIDGE 32 BIDS

We have reviewed the six bids received by the County for this project.

Milestone Contractors, LP has submitted the low base bid of \$3,946,000.00 and the low combination Base + Alternate 1 of \$3,954,528.00

The bid has been determined to be in order with no apparent unbalancing or other anomalies.

Both the Base and Base + Alternate are below the Engineer's estimates of \$4,189,708.86 and \$4,193,706.36 respectively.

We recommend that they be awarded the Project.

Prepared By:

Tippecanoe County Highway Department

Stewart W Kline, Executive Director

BID OF

MILESTONE CONTRACTORS, L.P. (Contractor)
3301 SOUTH CR 460 EAST
(Address)
LAFAYETTE, INDIANA 47905
FOR
PUBLIC WORKS PROJECTS
OF
The Tippecanoe County Board of Commissioners
Tippecanoe County Bridge No. 32 Replacement Contract
Filed March 1 , 2021
Action Taken

CONTRACT FOR PUBLIC WORK

THIS AGREEMENT, made and entered into by and between the BOARD OF COMMISSIONERS OF TIPPECANOE COUNTY, State of Indiana, as party of the first part hereinafter called the County and

Milestone Contractors, L.P.	3301 South 460 East	
(Name)	Lafayette, Indiana 47905	_
	(Address)	

as party of the second part, hereinafter called the Contractor:

WITNESSETH: That for and in consideration of the mutual covenant herein enumerated, the County does hereby hire and employ the Contractor to furnish all materials, equipment, and labor necessary and to fully construct the work designated as follows:

TIPPECANOE COUNTY BRIDGE NO. 32 REPLACEMENT CONTRACT

THE PROPOSED WORK CONSISTS OF REPLACING THE EXISTING BRIDGE WITH A 42 FT WIDE 3-SPAN PRESTRESSED CONCRETE BULB-TEE BEAM BRIDGE 302 FEET IN LENGTH, 2250 LINEAR FEET OF APPROACH ROADWAY RECONSTRUCTION ON CR 200 SOUTH, AND INCIDENTAL WORK. THE PROJECT WILL INCLUDE MAINTENANCE OF TRAFFIC, REMOVAL OF THE EXISTING STRUCTURE, CONSTRUCTION OF PILE-SUPPORTED PIERS AND BENTS, BEAM AND DECK PLACEMENT, TEMPORARY EROSION CONTROL MEASURES, EARTHWORK, DRAINAGE STRUCTURES, ASPHALT ROADWAY PAVEMENT, GUARDRAIL, PERMANENT EROSION CONTROL MEASURES, AND MITIGATION PLANTINGS.

		ns, profiles, and drawing		
specifications on file in the	office of said BOARD	OF COMMISSIONERS O	F TIPPECANOE COUN	TY and
any supplemental or specia	al provisions set out o	or referred to in the Cont	ractor's attached prop	osal, and
hereby agrees to pay the (Contractor therefore,	for the actual amount of	work done and mater	rials in
place, as measured by the	County Highway Eng	ineer, at the unit prices	stated in the Contracto	or's
attached proposal, dated _	March 1, 2021	, which b	ase bid sums in the ar	nount of
\$3,946,000.00	that the Contrac	tor agrees to accept in f	ull payment for such v	vork; and

It is further mutually agreed:

That the accompanying proposal and bond of the Contractor, together with the plans, standard and supplemental specifications and special provisions herein designated and referred to, are hereby made a part of the Contract, the same as if herein fully set forth;

The Contract amounts may be paid to the Contractor upon progress estimates of completed work, prepared by the Engineer, but progress payments shall not exceed ninety percent (90%) of any such estimates, less the total amount of properly prepared and certified statements of indebtedness which shall have been filed against the Contractor for labor performed and materials furnished, or other services rendered in the carrying forward, performing and completing this Contract, and which estimates shall also be subject to the provisions of the Standard Specifications on file in the office of said BOARD OF COMMISSIONERS OF TIPPECANOE COUNTY.

That before any final estimate is paid to the Contractor, he shall furnish receipt for all debts incurred in the prosecution of such work or satisfactory evidence and assurance that the same have been paid; or shall consent to the withholding by the County, from his final estimate, of sums sufficient to cover any such indebtedness, which sums may be held until such indebtedness is settled, or until the expiration of eighteen (18) months, or until the conclusion of any litigation in relation thereto filed within such period; and

That no monies due on this final estimate shall be paid until the work is fully completed and accepted as provided in the specifications nor until at least sixty-one (61) days after the last work and labor were performed and the last material furnished;

That the contract will be completed by the specified calendar date or liquidated damages will be assessed as provided for in the Special Provisions.

Witness our hands thisst	Witness our hands this
day of, 20_21	day of, 20
CONTRACTOR	BOARD OF COMMISSIONERS OF THE COUNTY OF TIPPECANOE
NAME: _Milestone Contractors, L.P.	
	Thomas P. Murtaugh, President
Address: 3301 South 460 East	David C. Divara Vice President
BY: Lafayette, IN 47905	David S. Byers, Vice President
Kenneth M. Walker, Director of Estimating	Tracy A. Brown, Member
SEAL 1953	ATTEST:
	Bob Plantenga, Auditor

CONTRACTOR'S BID FOR PUBLIC WORK - FORM 96

Slate Form 52414 (R2 /2-13) / Form 96 (Revised 2013) Prescribed by State Board of Accounts

PART I

(To be completed for all bids. Please type or print)

		Date: MARCH 1, 2021				
1.	Governmental Unit (Owner):	The Tippecanoe County Board of Commissioners				
2.	County:	Tippecanoe				
3.	Bidder (Firm):	MILESTONE CONTRACTORS, L.P.				
	Address:	3301 SOUTH CR 460 EAST				
	City/State:	LAFAYETTE, INDIANA 47905				
4	·					
4.	Telephone Number:	(765) 772-7500				
5.	Agent of Bidder (if applicable):	KENNETH M. WALKER				
Pursuant to notices given, the undersigned offers to furnish labor and/or material necessary to complete						
i uic	dant to notices given, the analys					
the public wo	orks project of The Tippecanoe Cou	unty Board of Commissioners				
(Governmen	tal Unit) in accordance with plans	s and specifications prepared by VS Engineering, Inc.				
		and dated for the sum of				
Son Attached P	id Proposal Form	\$				
See Allacijeu D	iu i Toposai i omi	•				

The undersigned further agrees to furnish a bond or certified check with this bid for an amount specified in the notice of the letting. If alternative bids apply, the undersigned submits a proposal for each in accordance with the notice. Any addendums attached will be specifically referenced at the applicable page.

If additional units of material included in the contract are needed, the cost of the units must be the same as that shown in the original contract if accepted by the governmental unit. If the bid is to be awarded on a unit basis, the itemization of the units shall be shown on a separate attachment.

The Contractor and his subcontractors, if any, shall not discriminate against or intimidate any employee, or applicant for employment, to be employed in the performance of this contract, with respect to any matter directly or indirectly related to employment because of race, religion, color, sex, national origin or ancestry. Breach of this covenant may be regarded as a material breach of the contract.

CERTIFICATION OF USE OF UNITED STATES STEEL PRODUCTS (if applicable)

I, the undersigned bidder or agent as a contractor on a public works project, understand my statutory obligation to use steel products made in the United States. (I.C. 5-16-8-2). I hereby certify that I and all subcontractors employed by me for this project will use U.S. steel products on this project if awarded. I understand that violations hereunder may result in forfeiture of contractual payments.

ACCEPTANCE

The above bid is accepted this	day of	,, subject to the following
conditions:		
Contracting Authority Members:		
(For pro	PART II ects of \$150,000 or more	e – (IC 36-1-12-4)
Governmental Unit:	The Tippecanoe County Board of Co	mmissioners
Bidder (Firm):	MILESTONE CONTRACTORS, L.P.	
Date (month, day, year):	MARCH 1, 2021	

These statements to be submitted under oath by each bidder with and as a part of his bid. Attach additional pages for each section as needed.

SECTION I EXPERIENCE QUESTIONNAIRE

1. What public works projects has your organization completed for the period of one (1) year prior to the date of the current bid?

Contract		Completion Date	
Amount	Class of Work	·	Name and Address of Owner
\$40,193,353.35	ROAD CONSTRUCTION	2020	INDIANA DEPARTMENT OF TRANSPORTATION, R-39272-A, 32
4 10,122,222			SOUTH BROADWAY ST., GREENFIELD, IN
\$7,716,557.00	ROAD CONSTRUCTION	2020	INDIANA DEPARTMENT OF TRANSPORTATION, R-39804-A, 41
ψ,,,,,ο,οσ,,,σσ			WEST 300 NORTH, CRAWFORDSVILLE, IN
\$6.689,503.26	ROAD CONSTRUCTION	2020	INDIANA DEPARTMENT OF TRANSPORTATION, RS-39251-A, 32
ψ0.000,000.20	1(0,12 00.10 11.10		SOUTH BROADWAY ST., GREENFIELD, IN
\$17,643,775.00	ROAD CONSTRUCTION	2020	INDIANA DEPARTMENT OF TRANSPORTATION, R-40020-A, 185
Ψ17,040,770.00			AGRICO LANE, SEYMOUR, IN

2. What public works projects are now in process of construction by your organization?

Contract Amount	Class of Work	Expected Completion Date	Name and Address of Owner
\$16,290,000.00	ROAD CONSTRUCTION	2021	INDIANA DEPARTMENT OF TRANSPORTATION, R-41265-A. 41 WEST 300 NORTH, CRAWFORDSVILLE, IN
\$3,864,132.00	ROAD CONSTRUCTION	2021	INDIANA DEPARTMENT OF TRANSPORTATION, B-38527-B, 32 SOUTH BROADWAY ST., GREENFIELD, IN
\$25,477,132.04	ROAD CONSTRUCTION	2021	INDIANA DEPARTMENT OF TRANSPORTION, R-40389-A, 185 AGRICO LANE, SEYMOUR, IN
\$13,184,000.00	ROAD CONSTRUCTION	2021	CITY OF BLOOMINGTON UTILITIES, JORDAN RIVER STORM CULVERT 600 E MILLER DRIVE, BLOOMINGTON, IN

List references from private firms for which you have performe DUNLAP AND COMPANY, INC. RH OF INDIANA F.A. WILHELM CONSTRUCTION CO., INC. J.R. KELLY COMPANY SECTION II PLAN AND EQUIPME! Explain your plan or layout for performing proposed work. (I	HOLLADAY CONSTRUCTION GROUP SHIEL SEXTON COMPANY, INC. SIGNATURE CONSTRUCTION
List references from private firms for which you have performe DUNLAP AND COMPANY, INC. RH OF INDIANA F.A. WILHELM CONSTRUCTION CO., INC. J.R. KELLY COMPANY SECTION II PLAN AND EQUIPMENT	od work. HOLLADAY CONSTRUCTION GROUP SHIEL SEXTON COMPANY, INC. SIGNATURE CONSTRUCTION
DUNLAP AND COMPANY, INC. RH OF INDIANA F.A. WILHELM CONSTRUCTION CO., INC. J.R. KELLY COMPANY SECTION II PLAN AND EQUIPMENT	HOLLADAY CONSTRUCTION GROUP SHIEL SEXTON COMPANY, INC. SIGNATURE CONSTRUCTION
RH OF INDIANA F.A. WILHELM CONSTRUCTION CO., INC. J.R. KELLY COMPANY SECTION II PLAN AND EQUIPMENT	SHIEL SEXTON COMPANY, INC. SIGNATURE CONSTRUCTION
RH OF INDIANA F.A. WILHELM CONSTRUCTION CO., INC. J.R. KELLY COMPANY SECTION II PLAN AND EQUIPMENT	SHIEL SEXTON COMPANY, INC. SIGNATURE CONSTRUCTION
F.A. WILHELM CONSTRUCTION CO., INC. J.R. KELLY COMPANY SECTION II PLAN AND EQUIPMENT	SIGNATURE CONSTRUCTION
SECTION II PLAN AND EQUIPME	
	NT OUESTIONNAIRE
WORK TO BE ASSIGNED TO A GENERAL SUPERINTENDENT WHO WI	LL HAVE DAY TO DAY RESPONSIBILITIES OF THE JOB.
Please list the names and addresses of all subcontractors (inhave performed part of the work) that you have used on publication with a brief description of the work done by each subcontractors.	olic works projects during the past five (5) years
SEE ATTACHED SUPPLEMENTAL	

3.	If you intend to sublet any portion of the work, state the name and address of each subcontractor, equipment to be used by the subcontractor, and whether you will require a bond. However, if you are unable to currently provide a listing, please understand a listing must be provided prior to contract approval. Until the completion of the proposed project, you are under a continuing obligation to immediately notify the governmental unit in the event that you subsequently determine that you will use a subcontractor on the proposed project.
	TO BE SUBMITTED UPON AWARD OF CONTRACT
4.	What equipment do you have available to use for the proposed project? Any equipment to be used by subcontractors may also be required to be listed by the governmental unit.
	SEE ATTACHED EQUIPMENT LIST. THE EQUIPMENT UTILIZED WILL BE THAT NECESSARY TO COMPLETE THE JOB.
•	
5.	Have you entered into contracts or received offers for all materials which substantiate the prices used in preparing your proposal? If not, please explain the rationale used which would corroborate the prices listed.
	YES WE HAVE RECEIVED OFFERS

SECTION III CONTRACTOR'S FINANCIAL STATEMENT

Attachment of bidder's financial statement is mandatory. Any bid submitted without said financial statement as required by statute shall thereby be rendered invalid. The financial statement provided hereunder to the governing body awarding the contract must be specific enough in detail so that said governing body can make a proper determination of the bidder's capability for completing the project if awarded.

SEE ATTACHED FINANCIAL STATEMENT

SECTION IV CONTRACTOR'S NON-COLLUSION AFFIDAVIT

The undersigned bidder or agent, being duly sworn on oath, says that he has not, nor has any other member, representative, or agent of the firm, company, corporation or partnership represented by him, entered into any combination, collusion or agreement with any person relative to the price to be bid by anyone at such letting nor to prevent any person from bidding nor to include anyone to refrain from bidding, and that this bid is made without reference to any other bid and without any agreement, understanding or combinaton with any other person in reference to such bidding.

He further says that no person or persons, firms, or corporation has, have or will receive directly or indirectly, any rebate, fee, gift, commission or thing of value on account of such sale.

SECTION V OATH AND AFFIRMATION

day of

MARCH

2021

I HEREBY AFFIRM UNDER THE PENALTIES FOR PERJURY THAT THE FACTS AND INFORMATION CONTAINED IN THE FOREGOING BID FOR PUBLIC WORKS ARE TRUE AND CORRECT.

this 1ST

Dated at LAFAYETTE, INDIANA	this	1 ST	_ day of	MARCH	,2021	
		M	ILESTONE	CONTRACTORS L.P. BY		
-		CONTRA		TED, INC - GENERAL PARTNER		
		11	(Ivairie	of Organization)	ANIMBINA.	
	Ву	h	utM.	Walker	SUNITED NO	
	• -	KENNET		ED DIDECTOR OF ESTIMATING	CEAL	
-		KENNET		ER, DIRECTOR OF ESTIMATING F Person Signing)	1953	
			(11110-01	T crock cigimig)	NO MAION CO	
					A STATE OF THE PARTY OF THE PAR	
,	ACKN	IOWLED	GMENT			
27.75.05		1111111				
STATE OF <u>INDIANA</u>)	11111111	NA L.	11,			
)ss:_	MASS	anoe C.	CONT.			
# <u>#</u>	TON	ARY PUBLIC	0			
COUNTY OF <u>TIPPECANOE</u>	Comm	n. # 672332				
	53	ommission.				
Before me, a Notary Public, personally appeared the above named Kenneth M. Walker and swore that the						
statements contained in the foregoing document	ent ar	e true ar	d correct.			
Culturalished and awarn to before me this 1ST d	lay of	MARCH	2021			
Subscribed and sworn to before me this 1^{ST} d	iay Ui	MARCH	, <u>2021</u> .	,		
			Thri	making & Malcon,		
			11 101	TUXUU OI. OVUSOTO		
				Notary Public THOMASINA L. NELSON		
My Commission Expires: AUGUST 30, 2023	3			THOMASINA L. NELSON		
My Commission Expires: AUGUST 30, 2023						
County of Residence: TIPPECANOE						
•						



Bid Bond

CONTRACTOR:

(Name, legal status and address)

Milestone Contractors, L.P. 3301 S 460 E Lafayette, IN 47905

OWNER:

(Name, legal status and address)

The Board of Commissioners of Tippecanoe County 20 North Third Street Lafayette, IN 47901

BOND AMOUNT: 5%

Five Percent of Amount Bid

PROJECT:

(Name, location or address, and Project number, if any)

Tippecanoe County Bridge No. 32 Replacement Contract

Bond No. Bid Bond

SURETY: Continental Casualty Company (Name, legal status and principal place of business)

151 N. Franklin Street 17th Floor Chicago, IL 60606

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this1St day of Warch	Milestone Contractors, L.P. By		1953 (M) (M) (M)
Thimaring of Mico	Contractors United, Inc General Partner	v	Manual Community
MUMASY W OY. JV EISON	(Principal)		(Seal)
(Witness) Thomasina L. Nelson	By: Kutt M. Walker		CHARLES
	(Title) Kenneth M. Walker, Director of Estimat	16	G STAROPACE
(1)	Continental Casualty Company	3/	CORPORATE) 2
White Work Lay	(Surety)	E	(Seal)
(Witness) Angela M. Riley	By: Karryal Reforms	187	SEAL /
	(Title) Kathryn R. Postma, Attorney-in-Fact	1	- Marian I
		TOP	1897

POWER OF ATTORNEY APPOINTING INDIVIDUAL ATTORNEY-IN-FACT

Know All Men By These Presents, That Continental Casualty Company, an Illinois insurance company, National Fire Insurance Company of Hartford, an Illinois insurance company, and American Casualty Company of Reading, Pennsylvania, a Pennsylvania insurance company (herein called "the CNA Companies"), are duly organized and existing insurance companies having their principal offices in the City of Chicago, and State of Illinois, and that they do by virtue of the signatures and seals herein affixed hereby make, constitute and appoint

Kathryn R. Postma, Individually

their true and lawful Attorney(s)-in-Fact with full power and authority hereby conferred to sign, seal and execute for and on of Indianapolis, IN their behalf bonds, undertakings and other obligatory instruments of similar nature

- In Unlimited Amounts -

Surety Bond No.:

Bid Bond

Principal: Milestone Contractors, L.P.

Obligee: The Board of Commissioners of Tippecanoe County

and to bind them thereby as fully and to the same extent as if such instruments were signed by a duly authorized officer of their insurance companies and all the acts of said Attorney, pursuant to the authority hereby given is hereby ratified and confirmed.

This Power of Attorney is made and executed pursuant to and by authority of the By-Law and Resolutions, printed on the reverse hereof, duly adopted, as indicated, by the Boards of Directors of the insurance companies.

In Witness Whereof, the CNA Companies have caused these presents to be signed by their Vice President and their corporate seals to be hereto affixed on this 27th day of February, 2018.







Continental Casualty Company National Fire Insurance Company of Hartford American Casualty Company of Reading, Pennsylvania

Paul T. Bruflat

ice President

State of South Dakota, County of Minnehaha, ss:

On this 27th day of February, 2018, before me personally came Paul T. Bruflat to me known, who, being by me duly sworn, did depose and say: that he resides in the City of Sioux Falls, State of South Dakota; that he is a Vice President of Continental Casualty Company, an Illinois insurance company, National Fire Insurance Company of Hartford, an Illinois insurance company, and American Casualty Company of Reading, Pennsylvania, a Pennsylvania insurance company described in and which executed the above instrument; that he knows the seals of said insurance companies; that the seals affixed to the said instrument are such corporate seals; that they were so affixed pursuant to authority given by the Boards of Directors of said insurance companies and that he signed his name thereto pursuant to like authority, and acknowledges same to be the act and deed of said insurance companies.



My Commission Expires June 23, 2021

Notary Public

CERTIFICATE

I, D. Johnson, Assistant Secretary of Continental Casualty Company, an Illinois insurance company, National Fire Insurance Company of Hartford, an Illinois insurance company, and American Casualty Company of Reading, Pennsylvania, a Pennsylvania insurance company do hereby certify that the Power of Attorney herein above set forth is still in force, and further certify that the By-Law and Resolution of the Board of Directors of the insurance companies printed on the reverse hereof is still in force. In testimony whereof I have hereunto subscribed my name and affixed the seal of the said insurance companies this 1st day of March, 2021.







Continental Casualty Company National Fire Insurance Company of Hartford American Casualty Company of Reading, Pennsylvania

D. Johnson

Assistant Secretary

Form F6853-4/2012

Authorizing By-Laws and Resolutions

ADOPTED BY THE BOARD OF DIRECTORS OF CONTINENTAL CASUALTY COMPANY:

This Power of Attorney is made and executed pursuant to and by authority of the following resolution duly adopted by the Board of Directors of the Company at a meeting held on May 12, 1995:

"RESOLVED: That any Senior or Group Vice President may authorize an officer to sign specific documents, agreements and instruments on behalf of the Company provided that the name of such authorized officer and a description of the documents, agreements or instruments that such officer may sign will be provided in writing by the Senior or Group Vice President to the Secretary of the Company prior to such execution becoming effective."

This Power of Attorney is signed by Paul T. Bruflat, Vice President, who has been authorized pursuant to the above resolution to execute power of attorneys on behalf of Continental Casualty Company.

This Power of Attorney is signed and sealed by facsimile under and by the authority of the following Resolution adopted by the Board of Directors of the Company by unanimous written consent dated the 25th day of April, 2012:

"Whereas, the bylaws of the Company or specific resolution of the Board of Directors has authorized various officers (the "Authorized Officers") to execute various policies, bonds, undertakings and other obligatory instruments of like nature; and

Whereas, from time to time, the signature of the Authorized Officers, in addition to being provided in original, hard copy format, may be provided via facsimile or otherwise in an electronic format (collectively, "Electronic Signatures"); Now therefore be it resolved: that the Electronic Signature of any Authorized Officer shall be valid and binding on the Company. "

ADOPTED BY THE BOARD OF DIRECTORS OF NATIONAL FIRE INSURANCE COMPANY OF HARTFORD:

This Power of Attorney is made and executed pursuant to and by authority of the following resolution duly adopted by the Board of Directors of the Company by unanimous written consent dated May 10, 1995:

"RESOLVED: That any Senior or Group Vice President may authorize an officer to sign specific documents, agreements and instruments on behalf of the Company provided that the name of such authorized officer and a description of the documents, agreements or instruments that such officer may sign will be provided in writing by the Senior or Group Vice President to the Secretary of the Company prior to such execution becoming effective."

This Power of Attorney is signed by Paul T. Bruflat, Vice President, who has been authorized pursuant to the above resolution to execute power of attorneys on behalf of National Fire Insurance Company of Hartford.

This Power of Attorney is signed and sealed by facsimile under and by the authority of the following Resolution adopted by the Board of Directors of the Company by unanimous written consent dated the 25th day of April, 2012:

"Whereas, the bylaws of the Company or specific resolution of the Board of Directors has authorized various officers (the "Authorized Officers") to execute various policies, bonds, undertakings and other obligatory instruments of like nature; and

Whereas, from time to time, the signature of the Authorized Officers, in addition to being provided in original, hard copy format, may be provided via facsimile or otherwise in an electronic format (collectively, "Electronic Signatures"); Now therefore be it resolved: that the Electronic Signature of any Authorized Officer shall be valid and binding on the Company. "

ADOPTED BY THE BOARD OF DIRECTORS OF AMERICAN CASUALTY COMPANY OF READING, PENNSYLVANIA:

This Power of Attorney is made and executed pursuant to and by authority of the following resolution duly adopted by the Board of Directors of the Company by unanimous written consent dated May 10, 1995:

"RESOLVED: That any Senior or Group Vice President may authorize an officer to sign specific documents, agreements and instruments on behalf of the Company provided that the name of such authorized officer and a description of the documents, agreements or instruments that such officer may sign will be provided in writing by the Senior or Group Vice President to the Secretary of the Company prior to such execution becoming effective."

This Power of Attorney is signed by Paul T. Bruflat, Vice President, who has been authorized pursuant to the above resolution to execute power of attorneys on behalf of American Casualty Company of Reading, Pennsylvania.

This Power of Attorney is signed and sealed by facsimile under and by the authority of the following Resolution adopted by the Board of Directors of the Company by unanimous written consent dated the 25th day of April, 2012:

"Whereas, the bylaws of the Company or specific resolution of the Board of Directors has authorized various officers (the "Authorized Officers") to execute various policies, bonds, undertakings and other obligatory instruments of like nature; and

Whereas, from time to time, the signature of the Authorized Officers, in addition to being provided in original, hard copy format, may be provided via facsimile or otherwise in an electronic format (collectively, "Electronic Signatures"); Now therefore be it resolved: that the Electronic Signature of any Authorized Officer shall be valid and binding on the Company. "

ITEM NO.	SPECIF. REF.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM PRICE
1	105	CONSTRUCTION ENGINEERING	LS	1	\$50,058.40	\$50,058.40
2	110	MOBILIZATION AND DEMOBILIZATION	LS	1	\$197,000.00	\$197,000.00
3	201	CLEARING RIGHT OF WAY	LS	1	\$105,000.00	\$105,000.00
4	202	STRUCTURES AND OBSTRUCTIONS, REMOVE	LS	1	\$111,000.00	\$111,000.00
5	202	PRESENT STRUCTURE, REMOVE	LS	1	\$127,000.00	\$127,000.00
6	202	GUARDRAIL, END TREATMENT, REMOVE	EACH	6	\$250.00	\$1,500.00
7	202	PIPE, REMOVE	LFT	199	\$20.00	\$3,980.00
8	203	EXCAVATION, COMMON	CYS	1,715	\$24.00	\$41,160.00
9	203	BORROW	CYS	5,260	\$25.00	\$131,500.00
10	203	EXCAVATION, WATERWAY	CYS	9,790	\$15.00	\$146,850.00
11	205	STORMWATER MANAGEMENT BUDGET	DOL	107,628	\$1.00	\$107,628.00
12	205	STORMWATER MANAGEMENT IMPLEMENTATION	LS	1	\$2,000.00	\$2,000.00
13	205	SWQCP PREPARATION	LS	1	\$7,500.00	\$7,500.00
14	206	EXCAVATION, WET	CYS	450	\$40.00	\$18,000.00
15	206	COFFERDAM	LS	1 12 744	\$195,000.00	\$195,000.00
16	207	SUBGRADE TREATMENT, TYPE IBC	SYS	12,714	\$7.00	\$88,998.00
17	207	SUBGRADE TREATMENT, TYPE IC	SYS	506	\$19.00	\$9,614.00
18	211	AGGREGATE FOR END BENT BACKFILL	CYS	66 411	\$97.00 \$20.00	\$6,402.00 \$8,220.00
19	211	STRUCTURAL BACKFILL, TYPE 1 GEOTEXTILE FOR SUBGRADE TYPE 2A	CYS SYS	277	\$3.00	\$831.00
20 21	214	COMPACTED AGGREGATE NO. 53	TON	5,068	\$20.00	\$101,360.00
22	301 303	COMPACTED AGGREGATE NO. 73	TON	10	\$55.00	\$550.00
23	302	SUBBASE FOR PCCP	CYS	42	\$110.00	\$4,620.00
24	401	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	TON	349	\$74.00	\$25,826.00
25	401	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	TON	533	\$74.00	\$39,442.00
26	401	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	TON	595	\$66.00	\$39,270.00
27	401	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	TON	1,266	\$66.00	\$83,556.00
28	401	QC/QA-HMA, 3, 64, BASE, 19.0 mm	TON	1,399	\$64.00	\$89,536.00
29	406	ASPHALT FOR TACK COAT	TON	5	\$100.00	
30	503	TERMINAL JOINT, TYPE HMA	LFT	79	\$200.00	\$15,800.00
31	601	GUARDRAIL, TRANSITION TYPE TGB	EACH	4	\$2,300.00	\$9,200.00
32	601	GUARDRAIL, TYPE 6 TERMINAL SYSTEM	EACH	1	\$2,300.00	\$2,300.00
33	601	GUARDRAIL, REMOVE	LFT	1,490	\$2.00	\$2,980.00
34	601	GUARDRAIL END TREATMENT, OS	EACH	3	\$2,700.00	\$8,100.00
35	601	GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	LFT	219	\$20.00	\$4,380.00
36	609	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	SYS	192	\$135.00	\$25,920.00
37	610	HMA FOR APPROACHES, TYPE B	TONS	198	\$85.00	\$16,830.00
38	611	MAILBOX ASSEMBLY, SINGLE	EACH	1	\$225.00	
39	615	MONUMENT, SECTION CORNER	EACH	1	\$670.00	
40	615	BENCH MARK POST	EACH	1	\$1,100.00	
41	615	BRONZE PLAQUE	EACH	1	\$1,300.00	
42	616	RIPRAP, CLASS 1	TON	965	\$75.00	
43	616	RIPRAP, REVETMENT	TON	149	\$50.00	
44	616	RIPRAP, UNIFORM	TON	112	\$52.00	
45	616	GEOTEXTILE FOR RIPRAP TYPE 1B	SYS	1,742	\$1.00	\$1,742.00

ITEM NO.	SPECIF. REF.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM PRICE
46	621	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	SYS	6	\$400.00	\$2,400.00
47	621	EROSION CONTROL BLANKET	SYS	6,462	\$2.00	\$12,924.00
48	621	SEED MIXTURE, NATIVE	LBS	19	\$460.00	\$8,740.00
49	621	SEED MIXTURE, COVER	LBS	85	\$6.50	\$552.50
50	621	SEED MIXTURE , R	LBS	1,055	\$5.50	\$5,802.50
51	621	MULCHING MATERIAL	TONS	6	\$665.00	\$3,990.00
52	621	WATER	kGAL	2	\$10.00	\$20.00
53	621	SODDING	SYS	606	\$7.00	\$4,242.00
54	622	SIGN, DO NOT MOW OR SPRAY	EACH	6	\$150.00	\$900.00
55	622	SEEDLING	EACH	1,812	\$10.00	\$18,120.00
56	701	PILE, STEEL H, HP 14 X 89	LFT	1,200	\$95.00	\$114,000.00
57	701	DYNAMIC PILE LOAD TEST	EACH	4	\$7,000.00	\$28,000.00
58	701	TEST PILE, DYNAMIC, PRODUCTION	LFT	158	\$40.00	\$6,320.00
59	701	TEST PILE, DYNAMIC, RESTRIKE	EACH	4	\$6,300.00	\$25,200.00
60	701	PILE SHOE, HP 14 X 89	EACH	40	\$145.00	\$5,800.00
61	701	PILE SHOE, HP 12 X 53	EACH	16	\$125.00	\$2,000.00
62	701	PILE, STEEL H HP 12 X 53	LFT	616	\$75.00	\$46,200.00
63	702	CONCRETE, A, SUPERSTRUCTURE	CYS	12.5	\$1,300.00	\$16,250.00
64	702	CONCRETE, A, SUBSTRUCTURE	CYS	146.8	\$950.00	\$139,460.00
65	702	CONCRETE, B, FOOTINGS	CYS	107.0	\$300.00	\$32,100.00
66	702	CONCRETE, C, SUBSTRUCTURE	CYS	38.0	\$1,000.00	\$38,000.00
67	703	REINFORCING BARS	LBS	28,976	\$1.00	\$28,976.00
68	703	REINFORCING BARS, EPOXY COATED	LBS	200,785	\$1.05	\$210,824.25
69	703	THREADED TIE BAR ASSEMBLY, EPOXY COATED	EACH	44	\$30.00	\$1,320.00
70	704	CONCRETE, C, SUPERSTRUCTURE	CYS	467.0	\$800.00	\$373,600.00
71	704	DECK DRAIN	EACH	4	\$750.00	\$3,000.00
72	706	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	EACH	4	\$1,900.00	\$7,600.00
73	706	RAILING, CONCRETE PF-1	LFT	604	\$60.00	\$36,240.00
74	707	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. X 48 IN.	LFT	1,500	\$385.00	\$577,500.00
75	709	SURFACE SEAL	LS	1	\$2,500.00	\$2,500.00
76	714	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT.	LFT	172	\$630.00	\$108,360.00
77	715	PIPE, TYPE 3 CIRCULAR 15 IN	LFT	66	\$70.00	\$4,620.00
78	715	PIPE, END BENT DRAIN, 6 IN.	LFT	122	\$28.00	\$3,416.00
79	715	PIPE END SECTION, DIA. 15 IN	EACH	2	\$600.00	\$1,200.00
80	720	CASTING, TYPE 7	EACH	1	\$750.00	\$750.00
81	724	PRE-COMPRESSED FOAM JOINT	LFT	79	\$75.00	\$5,925.00
82	801	ROAD CLOSURE SIGN ASSEMBLY	EACH	7	\$350.00	\$2,450.00
83	801	DETOUR ROUTE MARKER ASSEMBLY	EACH	27	\$100.00	\$2,700.00
84	801	CONSTRUCTION SIGN, A	EACH	7	\$140.00	\$980.00
85	801	MAINTAINING TRAFFIC	LSUM	1	\$85,000.00	\$85,000.00
86	801	BARRICADE, III-A	LFT	108	\$14.00	\$1,512.00

ITEM	SPECIF.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM PRICE
NO.	REF.					
1	105	CONSTRUCTION ENGINEERING	LS	1	\$50,058.40	\$50,058.40
2	110	MOBILIZATION AND DEMOBILIZATION	LS	1	\$197,000.00	\$197,000.00
3	201	CLEARING RIGHT OF WAY	LS	1	\$105,000.00	\$105,000.00
4	202	STRUCTURES AND OBSTRUCTIONS, REMOVE	LS	1	\$111,000.00	\$111,000.00
5	202	PRESENT STRUCTURE, REMOVE	LS	1	\$127,000.00	\$127,000.00
6	202	GUARDRAIL, END TREATMENT, REMOVE	EACH	6	\$250.00	\$1,500.00
7	202	PIPE, REMOVE	LFT	199	\$20.00	\$3,980.00
8	203	EXCAVATION, COMMON	CYS	1,715	\$24.00	\$41,160.00
9	203	BORROW	CYS	5,260	\$25.00	\$131,500.00
10	203	EXCAVATION, WATERWAY	CYS	9,790	\$15.00	\$146,850.00
11	205	STORMWATER MANAGEMENT BUDGET	DOL	107,628	\$1.00	\$107,628.00
12	205	STORMWATER MANAGEMENT IMPLEMENTATION	LS	11	\$2,000.00	\$2,000.00
13	205	SWQCP PREPARATION	LS	1	\$7,500.00	\$7,500.00
14	206	EXCAVATION, WET	CYS	450	\$40.00	\$18,000.00
15	206	COFFERDAM	LS	1	\$195,000.00	\$195,000.00
16	207	SUBGRADE TREATMENT, TYPE IBC	SYS	12,714	\$7.00	\$88,998.00
17	207	SUBGRADE TREATMENT, TYPE IC	SYS	506	\$19.00	\$9,614.00
18	211	AGGREGATE FOR END BENT BACKFILL	CYS	66	\$97.00	\$6,402.00
19	211	STRUCTURAL BACKFILL, TYPE 1	CYS	411	\$20.00	\$8,220.00
20	214	GEOTEXTILE FOR SUBGRADE TYPE 2A	SYS	277	\$3.00	\$831.00
21	301	COMPACTED AGGREGATE NO. 53	TON	5,068	\$20.00	\$101,360.00
22	303	COMPACTED AGGREGATE NO. 73	TON	10	\$55.00	\$550.00
23	302	SUBBASE FOR PCCP	CYS	42	\$110.00	\$4,620.00
24	401	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	TON	349	\$74.00	\$25,826.00
25	401	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	TON	533	\$74.00	\$39,442.00
26	401	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	TON	595	\$66.00	\$39,270.00
27	401	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	TON	1,266	\$66.00	\$83,556.00
28	401	QC/QA-HMA, 3, 64, BASE, 19.0 mm	TON	1,399	\$64.00	\$89,536.00
29	406	ASPHALT FOR TACK COAT	TON	5	\$100.00	\$500.00
30	503	TERMINAL JOINT, TYPE HMA	LFT	79	\$200.00	\$15,800.00
31	601	GUARDRAIL, TRANSITION TYPE TGB	EACH	4	\$2,300.00	\$9,200.00
32	601	GUARDRAIL, TYPE 6 TERMINAL SYSTEM	EACH	1	\$2,300.00	\$2,300.00
33	601	GUARDRAIL, REMOVE	LFT	1,490	\$2.00	\$2,980.00
34	601	GUARDRAIL END TREATMENT, OS	EACH	3	\$2,700.00	\$8,100.00
35	601	GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	LFT	219	\$20.00	\$4,380.00
36	609	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	SYS	192	\$135.00	\$25,920.00
37	610	HMA FOR APPROACHES, TYPE B	TONS	198	\$85.00	\$16,830.00
38	611	MAILBOX ASSEMBLY, SINGLE	EACH	1	\$225.00	\$225.00
39	615	MONUMENT, SECTION CORNER	EACH	1	\$670.00	\$670.00
40	615	BENCH MARK POST	EACH	1	\$1,100.00	\$1,100.00
41	615	BRONZE PLAQUE	EACH	1	\$1,300.00	\$1,300.00
42	616	RIPRAP, CLASS 1	TON	965	\$75.00	\$72,375.00
43	616	RIPRAP, REVETMENT	TON	149	\$50.00	\$7,450.00
44	616	RIPRAP, UNIFORM	TON	112	\$52.00	\$5,824.00
45	616	GEOTEXTILE FOR RIPRAP TYPE 1B	SYS	1,742	\$1.00	\$1,742.00

66 621 MOBILIZATION AND DEMOBILIZATION FOR SEEDING SYS 6,462 \$2.00 \$12,91	ITEM NO.	SPECIF. REF.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM PRICE
48 621 SEED MIXTURE, NATIVE 49 621 SEED MIXTURE, COVER 185 85 56.50 \$5.5 50 621 SEED MIXTURE, R 188 1,055 \$5.50 \$5.8 51 621 MULCHING MATERIAL TONS 6 \$665.00 \$3.9 52 621 WATER KGAL 2 \$10.00 \$5.5 53 621 SODDING SYS 606 \$7.00 \$4.2 54 622 SIGN, DO NOT MOW OR SPRAY EACH 6 \$150.00 \$9.5 55 622 SEEDLING EACH 1,812 \$10.00 \$18.1 56 701 PILE, STEEL H, HP 14 X 89 LFT 1,200 \$50.00 \$11.4 57 701 DYNAMIC, PRODUCTION LET 158 \$40.00 \$2.8 58 701 TEST PILE, DYNAMIC, RESTRIKE EACH 4 \$7.000.00 \$2.8 60 701 PILE SHOE, HP 12 X 53 EACH 16 \$155.00 \$5.8 61 701 PILE, STEEL H, HP 12 X 53 EACH 16 \$155.00 \$5.8 62 701 PILE, STEEL H, HP 12 X 53 EACH 16 \$155.00 \$5.8 63 702 CONCRETE, A, SUBESTRUCTURE CVS 166 702 CONCRETE, A, SUBESTRUCTURE CVS 166 702 CONCRETE, A, SUBSTRUCTURE CVS 167 703 REINFORCING BARS, EPOXY COATED 188 28,976 \$1.00 \$2.0 68 703 REINFORCING BARS, EPOXY COATED 188 28,976 \$1.00 \$2.0 69 703 THREADED THE BAR ASSEMBLY 70 TIS PILE, TYRE AIL ING TRANSITION, TPF-1 LET 404 \$6.00.00 \$3.9 53.00 \$3.9 54.00 \$3.9 55.00 \$46.2 57.00 \$46.2 57.00 \$40.			MOBILIZATION AND DEMOBILIZATION FOR SEEDING	SYS	6	\$400.00	\$2,400.00
49 621 SEED MIXTURE, COVER LBS 85 \$6.50 \$5.50 \$5.50 \$5.50 \$6.21 \$5.50 \$6.21 \$5.50 \$6.21 \$5.50 \$6.21 \$5.50 \$6.25 \$5.50	47	621	EROSION CONTROL BLANKET	SYS	6,462	\$2.00	\$12,924.00
SEED MIXTURE R	48	621	SEED MIXTURE, NATIVE	LBS	19	\$460.00	\$8,740.00
51 621 MULCHING MATERIAL TONS 6 \$665.00 \$3.9 52 621 WATER K6AL 2 \$10.00 \$7.00 \$4.2 53 621 SODDING SYS 606 \$7.00 \$4.2 54 622 SIGN, DO NOT MOW OR SPRAY EACH 6 \$150.00 \$19.5 55 622 SEEDLING EACH 1,812 \$10.00 \$18,1 56 701 PILE, STEEL H, HP 14 X 89 LFT 1,200 \$95.00 \$114,00 57 701 DYNAMIC PILE LODA TEST EACH 4 \$7,000.00 \$28,00 58 701 TEST PILE, DYNAMIC, PRODUCTION LFT 158 \$40.00 \$6.3 597 701 TEST PILE, DYNAMIC, RESTRIKE EACH 4 \$6,300.00 \$25.20 60 701 PILE SHOE, HP 12 X 53 EACH 4 \$6,300.00 \$25.20 61 701 PILE, STEEL H HP 12 X 53 LFT 616 \$75.00	49	621	SEED MIXTURE, COVER	LBS	85	\$6.50	\$552.50
51 621 MULCHING MATERIAL TONS 6 \$665.00 \$3,9 52 621 WATER KGAL 2 \$10.00 \$,5 53 621 SODDING SYS 606 \$7.00 \$4,2 54 622 SIGN, DO NOT MOW OR SPRAY EACH 6 \$150.00 \$9 55 622 SEEDLING EACH 1,812 \$10.00 \$114,0 56 701 PILE, STEEL H, HP 14 X 89 LFT 1,200 \$95,00 \$114,0 57 701 DYNAMIC PILE LOAD TEST EACH 4 \$7,000.00 \$22,0 58 701 TEST PILE, DYNAMIC, RESTRIKE EACH 4 \$6,300.00 \$25,2 60 701 PILE SHOE, HP 14 X 89 EACH 4 \$6,300.00 \$25,2 61 701 PILE, STEEL H HP 12 X 53 LET 616 \$75.00 \$20,0 62 701 PILE, STEEL H HP 12 X 53 LET 616 \$75.00 \$36,2 <td>50</td> <td>621</td> <td>SEED MIXTURE , R</td> <td>LBS</td> <td>1,055</td> <td>\$5.50</td> <td>\$5,802.50</td>	50	621	SEED MIXTURE , R	LBS	1,055	\$5.50	\$5,802.50
53 621 SODDING SYS 606 \$7.00 \$4,2 54 622 SIGN, DO NOT MOW OR SPRAY EACH 6 \$150.00 \$9 55 622 SEDLING EACH 1,812 \$10.00 \$18,1 56 701 PIEL, STEEL H, HP 14 X 89 LFT 1,200 \$95.00 \$114,0 57 701 DYNAMIC PIEL LOAD TEST EACH 4 \$7,000.00 \$28,0 58 701 TEST PIEL, DYNAMIC, RESTRIKE EACH 4 \$6,300.00 \$25,2 60 701 PIEL, STEEL H. PI 2X 53 EACH 40 \$145.00 \$5,8 61 701 PIEL, STEEL H. PI 2X 53 EACH 16 \$125.00 \$20,0 62 701 PIE, STEEL H. PI 2X 53 LFT 616 \$75.00 \$46,2 63 702 CONCRETE, A, SUBSTRUCTURE CYS 12.5 \$1,300.00 \$16,2 64 702 CONCRETE, G, SUBSTRUCTURE CYS 146.8 \$950.00<	51	621	MULCHING MATERIAL	TONS	6	\$665.00	\$3,990.00
54 622 SIGN, DO NOT MOW OR SPRAY EACH 6 \$150.00 \$99 55 622 SEEDLING EACH 1,812 \$10.00 \$181,1 56 701 PILE, STEEL H, HP 14 X 89 LFT 1,200 \$95.00 \$114,0 57 701 DYNAMIC PILE LOAD TEST EACH 4 \$7,000.00 \$28,0 58 701 TEST PILE, DYNAMIC, RESTRIKE EACH 4 \$6,300.00 \$25,2 60 701 PILE SHOE, HP 14 X 89 EACH 40 \$145,00 \$5,8 61 701 PILE SHOE, HP 12 X 53 EACH 16 \$125,00 \$2,0 62 701 PILE, STEEL H HP 12 X 53 LFT 616 \$75,00 \$46,2 63 702 CONCRETE, A, SUBSTRUCTURE CYS 12.5 \$1,300.00 \$132,4 64 702 CONCRETE, B, FOOTINGS CYS 107.0 \$300.00 \$32,1 65 702 CONCRETE, Q, SUBSTRUCTURE CYS 38.0	52	621	WATER	kGAL	2	\$10.00	\$20.00
S55 622 SEEDLING	53	621	SODDING	SYS	606	\$7.00	\$4,242.00
Second	54	622	SIGN, DO NOT MOW OR SPRAY	EACH	6	\$150.00	\$900.00
57 701 DYNAMIC PILE LOAD TEST EACH 4 \$7,000.00 \$28,00 58 701 TEST PILE, DYNAMIC, PRODUCTION LFT 158 \$40.00 \$6,3 59 701 TEST PILE, DYNAMIC, RESTRIKE EACH 4 \$6,300.00 \$25,2 60 701 PILE SHOE, HP 14 X 89 EACH 40 \$145,00 \$5,8 61 701 PILE SHOE, HP 12 X 53 EACH 16 \$125,00 \$2,0 62 701 PILE, STEEL H HP 12 X 53 LFT 616 \$75.00 \$46,2 63 702 CONCRETE, A, SUPERSTRUCTURE CVS 12.5 \$1,300.00 \$132,4 64 702 CONCRETE, A, SUBSTRUCTURE CVS 146.8 \$950.00 \$321,1 65 702 CONCRETE, C, SUBSTRUCTURE CVS 146.8 \$950.00 \$330,0 66 702 CONCRETE, C, SUBSTRUCTURE CVS 38.0 \$1,000.00 \$38,0 67 703 REINFORCING BARS LBS	55	622	SEEDLING	EACH	1,812	\$10.00	\$18,120.00
S8	56	701	PILE, STEEL H, HP 14 X 89	LFT	1,200	\$95.00	\$114,000.00
S9	57	701	DYNAMIC PILE LOAD TEST	EACH	4	\$7,000.00	\$28,000.00
Fig.	58 /	701	TEST PILE, DYNAMIC, PRODUCTION	LFT	158		\$6,320.00
61 701 PILE SHOE, HP 12 X 53 EACH 16 \$125.00 \$2,0 62 701 PILE, STEEL H HP 12 X 53 LFT 616 \$75.00 \$46,21 63 702 CONCRETE, A, SUBERSTRUCTURE CYS 12.5 \$1,300.00 \$16,2 64 702 CONCRETE, A, SUBSTRUCTURE CYS 146.8 \$950.00 \$139,4 65 702 CONCRETE, B, FOOTINGS CYS 107.0 \$300.00 \$32,1 66 702 CONCRETE, C, SUBSTRUCTURE CYS 38.0 \$1,000.00 \$38,0 67 703 REINFORCING BARS LBS 28,976 \$1.00 \$28,9 68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$210,8 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH	59	701	TEST PILE, DYNAMIC, RESTRIKE	EACH	4		\$25,200.00
Fig.	60	701	PILE SHOE, HP 14 X 89	EACH	40		\$5,800.00
63 702 CONCRETE, A, SUPERSTRUCTURE CYS 12.5 \$1,300.00 \$16,2 64 702 CONCRETE, A, SUBSTRUCTURE CYS 146.8 \$950.00 \$139,4 65 702 CONCRETE, B, FOOTINGS CYS 107.0 \$300.00 \$32,1 66 702 CONCRETE, C, SUBSTRUCTURE CYS 38.0 \$1,000.00 \$38,0 67 703 REINFORCING BARS LBS 28,976 \$1.00 \$22,99 68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$221,9 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 <td>61</td> <td>701</td> <td>PILE SHOE, HP 12 X 53</td> <td>EACH</td> <td>16</td> <td>\$125.00</td> <td>\$2,000.00</td>	61	701	PILE SHOE, HP 12 X 53	EACH	16	\$125.00	\$2,000.00
64 702 CONCRETE, A, SUBSTRUCTURE CYS 146.8 \$950.00 \$139,4 65 702 CONCRETE, B, FOOTINGS CYS 107.0 \$300.00 \$32,1 66 702 CONCRETE, C, SUBSTRUCTURE CYS 38.0 \$1,000.00 \$38,0 67 703 REINFORCING BARS LBS 28,976 \$1.00 \$28,9 68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$210,8 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEA	62	701	PILE, STEEL H HP 12 X 53	LFT	616		\$46,200.00
65 702 CONCRETE, B, FOOTINGS CYS 107.0 \$300.00 \$32,1 66 702 CONCRETE, C, SUBSTRUCTURE CYS 38.0 \$1,000.00 \$38,0 67 703 REINFORCING BARS LBS 28,976 \$1.00 \$28,9 68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$210,8 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 IN. X 48 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS <td< td=""><td>63</td><td>702</td><td>CONCRETE, A, SUPERSTRUCTURE</td><td>CYS</td><td>12.5</td><td></td><td>\$16,250.00</td></td<>	63	702	CONCRETE, A, SUPERSTRUCTURE	CYS	12.5		\$16,250.00
66 702 CONCRETE, C, SUBSTRUCTURE CYS 38.0 \$1,000.00 \$38,0 67 703 REINFORCING BARS LBS 28,976 \$1.00 \$28,9 68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$210,8 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONC	64	702	CONCRETE, A, SUBSTRUCTURE	CYS	146.8		\$139,460.00
67 703 REINFORCING BARS LBS 28,976 \$1.00 \$28,9 68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$210,8 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. X 48 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 <td>65</td> <td>702</td> <td>CONCRETE, B, FOOTINGS</td> <td>CYS</td> <td>107.0</td> <td>\$300.00</td> <td>\$32,100.00</td>	65	702	CONCRETE, B, FOOTINGS	CYS	107.0	\$300.00	\$32,100.00
68 703 REINFORCING BARS, EPOXY COATED LBS 200,785 \$1.05 \$210,8 69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 65 \$70.00 \$4,6 78 715	66	702	CONCRETE, C, SUBSTRUCTURE	CYS	38.0	\$1,000.00	\$38,000.00
69 703 THREADED TIE BAR ASSEMBLY, EPOXY COATED EACH 44 \$30.00 \$1,3 70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,6 71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 172 \$630.00 \$108,3 79 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 80 720	67	703	REINFORCING BARS	LBS	28,976	\$1.00	\$28,976.00
70 704 CONCRETE, C, SUPERSTRUCTURE CYS 467.0 \$800.00 \$373,60 71 704 DECK DRAIN EACH 4 \$750.00 \$3,00 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,60 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. LFT LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 172 \$630.00 \$108,3 79 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720	68	703	REINFORCING BARS, EPOXY COATED	LBS	200,785	\$1.05	\$210,824.25
71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. X 48 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 66 \$70.00 \$4,6 78 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED F	69	703	THREADED TIE BAR ASSEMBLY, EPOXY COATED	EACH	44	\$30.00	\$1,320.00
71 704 DECK DRAIN EACH 4 \$750.00 \$3,0 72 706 CONCRETE BRIDGE RAILING TRANSITION, TPF-1 EACH 4 \$1,900.00 \$7,6 73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. X 48 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 172 \$630.00 \$108,3 79 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE, END BECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRES	70	704	CONCRETE, C, SUPERSTRUCTURE	CYS	467.0	\$800.00	\$373,600.00
73 706 RAILING, CONCRETE PF-1 LFT 604 \$60.00 \$36,2 74 707 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 66 IN. X 48 IN. LFT 1,500 \$385.00 \$577,5 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 66 \$70.00 \$4,6 78 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER	71	704		EACH	4	\$750.00	\$3,000.00
Total Structural Member, Concrete, Bulb-T Beam, 66 LFT 1,500 \$385.00 \$577,50 \$709 \$Surface Seal LS 1 \$2,500.00 \$2,50	72	706	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	EACH	4	\$1,900.00	\$7,600.00
74 707 IN. X 48 IN. LFT 1,500 \$385.00 \$577,50 75 709 SURFACE SEAL LS 1 \$2,500.00 \$2,5 76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 66 \$70.00 \$4,6 78 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 7 \$140.00 \$9 84 801 CONSTRUCTION SIGN, A EACH	73	706	RAILING, CONCRETE PF-1	LFT	604	\$60.00	\$36,240.00
76 714 STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT. LFT 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 66 \$70.00 \$4,6 78 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	74	707		LFT	1,500	\$385.00	\$577,500.00
76 714 FT. X 4 FT. LFI 172 \$630.00 \$108,3 77 715 PIPE, TYPE 3 CIRCULAR 15 IN LFT 66 \$70.00 \$4,6 78 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	75	709		LS	1	\$2,500.00	\$2,500.00
78 715 PIPE, END BENT DRAIN, 6 IN. LFT 122 \$28.00 \$3,4 79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	76	714		LFT	172	\$630.00	\$108,360.00
79 715 PIPE END SECTION, DIA. 15 IN EACH 2 \$600.00 \$1,2 80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	77	715	PIPE, TYPE 3 CIRCULAR 15 IN	LFT	66	\$70.00	\$4,620.00
80 720 CASTING, TYPE 7 EACH 1 \$750.00 \$7 81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	78	715	PIPE, END BENT DRAIN, 6 IN.	LFT	122	\$28.00	\$3,416.00
81 724 PRE-COMPRESSED FOAM JOINT LFT 79 \$75.00 \$5,9 82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	79	715	PIPE END SECTION, DIA. 15 IN	EACH	2	\$600.00	\$1,200.00
82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 .83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9	80	720	CASTING, TYPE 7	EACH	1	\$750.00	\$750.00
82 801 ROAD CLOSURE SIGN ASSEMBLY EACH 7 \$350.00 \$2,4 .83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,7 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9				LFT	79	\$75.00	\$5,925.00
83 801 DETOUR ROUTE MARKER ASSEMBLY EACH 27 \$100.00 \$2,70 84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9				EACH	7	\$350.00	\$2,450.00
84 801 CONSTRUCTION SIGN, A EACH 7 \$140.00 \$9					27		\$2,700.00
407.000.00				 			\$980.00
85 801 MAINTAINING TRAFFIC LSUM 1 \$85,000.00 \$85,0				LSUM	1	\$85,000.00	
							\$1,512.00

ITEM NO.	SPECIF. REF.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM PRICE
87	801	BARRICADE, III-B	LFT	96	\$14.00	\$1,344.00
88	802	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	LFT	118	\$18.00	\$2,124.00
89	802	SIGN, SHEET, WITH LEGEND 0.080"	SFT	43	\$27.00	\$1,161.00
90	802	SIGN GROUND MOUNTED RESET	EACH	2	\$160.00	\$320.00
91	808	LINE, PAINT, SOLID, WHITE, 4 IN	LFT	5,454	\$0.35	\$1,908.90
92	808	LINE, PAINT, SOLID, YELLOW, 4 IN	LFT	2,637	\$0.35	\$922.95
93	808	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN. STOP LINE, 24"	LFT	44	\$8.00	\$352.00
94	808	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT	684	\$3.50	\$2,394.00
95	808	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT	684	\$3.50	\$2,394.00
96	706	RAILING, STEEL PF-1	LFT	621.25	\$70.00	\$43,487.50
TOTAL BASE BID						\$3,946,000.00

Alternate No. 1: The price for Alternate 1 shall represent the **addition or deduction** for substituting QC/QA-HMA-SMA for the QC/QA-HMA surface course for all mainline pavement. Additions shall be shown without parentheses, and deductions shall be shown with parentheses: \$X.XX for Addition (\$X.XX) for Deduction

A1 401/410 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm , SMA TO	ONS	533	\$16.00	\$8,528.00
---	-----	-----	---------	------------

SUBMITTED BY:

CONTRACTOR NAME: Milestone Contractors L.P.

DATE: 3/1/2021

THE BIDDER ACKNOWLEDGES RECEIPT OF THE FOLLOWING ADDENDA:

ADDENDUM NO.: $\underline{1}$ DATED: $\underline{2/8/2021}$ ADDENDUM NO.: $\underline{2}$ DATED : $\underline{2/9/2021}$ ADDENDUM NO.: $\underline{3}$ DATED: $\underline{2/22/2021}$



ITEM NO.	SPECIF. REF.	DESCRIPTION	UNIT	QTY.	UNIT PRICE	ITEM PRICE
87	801	BARRICADE, III-B	LFT	96	\$14.00	\$1,344.00
88	802	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	LFT	118	\$18.00	\$2,124.00
89	802	SIGN, SHEET, WITH LEGEND 0.080"	SFT	43	\$27.00	\$1,161.00
90	802	SIGN GROUND MOUNTED RESET	EACH	2	\$160.00	\$320.00
91	808	LINE, PAINT, SOLID, WHITE, 4 IN	LFT	5,454	\$0.35	\$1,908.90
92	808	LINE, PAINT, SOLID, YELLOW, 4 IN	LFT	2,637	\$0.35	\$922.95
93	808	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN. STOP LINE, 24"	LFT	44	\$8.00	\$352.00
94	808	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT	684	\$3.50	\$2,394.00
95	808	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT	684	\$3.50	\$2,394.00
96	706	RAILING, STEEL PF-1	LFT	621.25	\$70.00	\$43,487.50
	TOTAL BASE BID					

Alternate No. 1: The price for Alternate 1 shall represent the **addition or deduction** for substituting QC/QA-HMA-SMA for the QC/QA-HMA surface course for all mainline pavement. Additions shall be shown without parentheses, and deductions shall be shown with parentheses: \$X.XX for Addition (\$X.XX) for Deduction

A1	401/410 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm , SMA	TONS	533	\$16.00	\$8,528.00

SUBMITTED BY:

AUTHORIZED SIGNATURE:

CONTRACTOR NAME: Milestone Contractors L.P.

THE BIDDER ACKNOWLEDGES RECEIPT OF THE FOLLOWING ADDENDA:

ADDENDUM NO.: 1 DATED: 2/8/2021 ADDENDUM NO.: 2 DATED: 2/9/2021 ADDENDUM NO.: 3 DATED: 2/22/2021

SEAL POST

DATE: <u>3/1/2021</u>